

Reduce your Electric Bills.



65 kVAR

Total capacity

480 V

3-Phase, 60 Hz

7 steps

Individually controlled

400 A

Suitable facility

MODEL

M-65

Full Load Current
Operating ambient
Dimensions
Mounting
Weight Net/Gross
Sensing
kVAR Steps

79 A
Up to 104°F
24" x 30"
Wall mounting
123 / 137 lbs
Split core Current Sensor
2, 3, 5, 10, 15, 15, 15

Auto-selects the optimal capacitor combinations.
Maintains target power factor in real time.
Individual switching of each capacitor.
Installs at the main panel in under 4 hrs.

Controlled by Celec Digital Power Factor Regulator



Reduced
Electric Bills



Lower Demand
Charges



AI Cloud
Power Logger



Surge
Suppression



Budget
Friendly



www.celec.com

