

Reduce your Electric Bills.



25 kVAR

Total capacity

208 V

3-Phase, 60 Hz

5 steps

Individually controlled

400 A

Suitable facility

MODEL

S-25

Full Load Current
Operating ambient
Dimensions
Mounting
Weight Net/Gross
Sensing
kVAR Steps

70 A
Up to 104°F
24" x 30"
Wall mounting
121 / 132 lbs
Split core Current Sensor
2, 4, 6, 6, 6

Auto-selects the optimal capacitor combinations.
Maintains target power factor in real time.
Individual switching of each capacitor.
Installs at the main panel in under 4 hrs.

Controlled by Celec Digital Power Factor Regulator



Reduced
Electric Bills



Lower Demand
Charges



AI Cloud
Power Logger



Surge
Suppression



Budget
Friendly



www.celec.com

