



Reduce your Electric Bills.

50 kVAR

Total capacity

208 V

3-Phase, 60 Hz

7 steps

Individually controlled

600 A

Suitable facility

MODEL

S-50

Full Load Current
Operating ambient
Dimensions
Mounting
Weight Net/Gross
Sensing
kVAR Steps

140 A
Up to 104°F
32" x 40"
Floor mounting
216 / 275 lbs
Split core Current Sensor
3, 5, 8.3, 8.3, 8.3, 8.3

Auto-selects the optimal capacitor combinations.
Maintains target power factor in real time.
Individual switching of each capacitor.
Installs at the main panel in under 6 hrs.

Controlled by Celec Digital Power Factor Regulator



Reduced
Electric Bills



Lower Demand
Charges



AI Cloud
Power Logger



Surge
Suppression



Budget
Friendly



www.celec.com

